TABLE OF CONTENTS

Page

14. SUMMARY OF ENVIRONMENTAL OUTCOMES 14-1

14.1 Introduction.....14-1
14.2 Environmental Benefits and Environmentally Friendly Design 14-1
14.3 Other Environmental Design Recommended.....14-3
14.4 Key Environmental Problem Avoided and Environmentally Sensitive Areas Protected 14-4
14.5 Environmental Protection Measures Recommended 14-6
14.6 Population and Environmentally Sensitive Areas Protected.....14-13

List of Table

Table 14.1 Summary of Key Environmental Issues Avoided / Minimised and Sensitive Areas Protected
Table 14.2 Summary of Key Recommended Mitigation Measures / Good Site Practices / Enhancement Measures and their Associated Benefits

14. SUMMARY OF ENVIRONMENTAL OUTCOMES

14.1 Introduction

14.1.1.1 **Section 2** outlines the details and benefits of the Project together with the consideration of alternatives during the investigation stage, which has taken into account public concerns and findings of various engineering and environmental review. The technical assessments in **Sections 3** to **12** have demonstrated that all the statutory requirements in the Study Brief No. ESB-373/2025 under the Environmental Impact Assessment Ordinance (EIAO) and the Technical Memorandum on Environmental Impact Assessment Process (EIAO-TM) have been complied with.

14.1.1.2 This chapter summarises the key environmental outcomes arising from this Environmental Impact Assessment (EIA) study, the approaches that have been adopted to either avoid or minimise various environmental impacts throughout the design process, and the associated environmental enhancements and mitigation measures.

14.2 Environmental Benefits and Environmentally Friendly Design

14.2.1.1 The Project can bring the following benefits:

Avoidance of direct impact to ecologically sensitive areas

14.2.1.2 The recommended alignment and its works footprint have been thoroughly considered, evaluated from alternative alignment options proposed in previous stage studies (**Section 2.6** refers). This process has resulted in the recommended alignment option, which aims to avoid both direct and indirect potential impacts on recognised sites of conservation importance and other ecologically sensitive areas, such as the Lam Tsuen Country Park (LTCP), the proposed Nam Sang Wai Wetland Conservation Park and natural watercourses at Ngau Tam Mei. The locations of piers are also carefully designed to be outside the Ngau Tam Mei natural watercourses.

Wetland Habitat Enhancement through Integration and Expansion

14.2.1.3 Under the original alignment, an interchange, I/C-03, (with associated site office and ancillary facilities) was proposed to the west Ngau Tam Mei Water Treatment Works (NTMWTW), where scattered and fragmented wetland habitats are currently found. Compared to the original alignment, the recommended alignment has been refined, with the Interchange I/C-03 relocated to the south of Ngau Tam Mei New Development Area (NTM NDA). The viaduct level has also been raised as much as practicable to provide greater clearance allowing natural sunlight to reach the habitats underneath the viaduct structures. The relocation of Interchange I/C-03 to the south of NTM NDA will also provide an opportunity to integrate and expand the wetland habitats to the west of NTMWTW. Furthermore, the mainline will be constructed as an elevated viaduct with a limited number of piers, spanning over the wetland habitats to reduce direct ecological impact to this wetland habitats. Taking advantage of the Project implementation, the area will not only be reinstated, but the existing fragmented wetland habitats will also be integrated and enhanced into a connected wetland habitat. The total wetland area will increase from approximately 3 hectares of fragmented ponds to more than 5 hectares of integrated wetland habitats through the incorporation of adjacent village / orchard

land. With improved design and management, the enhanced wetland habitat will support higher biodiversity, greater ecological value and increased carrying capacity. It will also offer a suitable foraging environment for various relevant species, including waterbirds.

Allowing Wildlife Movement by Adopting Intermittent At-grade and Viaduct Design

14.2.1.4 A section of the alignment runs adjacent to the woodland habitat at the edge of the Lam Tsuen Country Park (LTCP) near Long Ha. The alignment profile has been raised as far as practicable, taking into account site constraints such as CLP cables, pylons and traffic design requirements. The design has been optimised to avoid encroachment into LTCP while maximising the length of the viaduct section (Ratio of at-grade, tunnel, and viaduct is 1:1.14:1.95). Each of the at-grade sections is no greater than ~350 m so as to avoid creating potential hurdles to wildlife movement. The space beneath the viaduct sections provides an open corridor to facilitate wildlife movement to and from LTCP. For the at-grade sections, retaining wall on the slope would be constructed to avoid wildlife roadkill.

Viaduct Level Arrangement and Carriageway Separation for Enhancing Sunlight Penetration and Ecological Benefits

14.2.1.5 The Project includes slip roads crossing the Kam Tin River, where the viaduct level has been adjusted to provide headroom of about 10~15m and minimise shading effects on the water body and associated habitats. In the vicinity of NTMWTW, to accommodate the required clearance from the existing CLP cable, the headroom beneath the viaduct is approximately 10m for the northbound and ranges from 5m to 10m for the southbound. The dual carriageways are separated before entering the tunnel portal. The resulting gap between the carriageways enables natural sunlight to reach the ground below and is not expected to cause adverse ecological impacts. Furthermore, the positioning of piers have been refined to avoid encroachment into natural watercourses. This approach helps to minimize potential water quality and ecological impact.

Adoption of non-dredged method for construction works at Kam Tin River

14.2.1.6 The significance of ecological value of Kam Tin River is well recognised. Given the large span of the viaduct crossing Kam Tin River, the pile /pier support within the river is inevitable. The construction of viaduct pier/ pile will adopt the non-dredging method. For example, if bored pile construction is adopted, steel casing could be adopted to isolate the surrounding riverbed. The material within the steel casing will be excavated within the casing for placing reinforcement and concrete of the pile. This minimises the disturbance to the river.

Synergistic Woodland Enhancement near She Leng

14.2.1.7 A woodland compensation of approximately 17 ha is proposed near She Leng, which is currently characterised by grassland or shrubland of low or low to moderate ecological value. The site is also adjacent to proposed woodland compensation areas under other projects, including Lok Ma Chau Loop, San Tin Technopole (STT) and Development of the Loop – Eastern Connection Road (ECR). Woodland compensation at this location will integrate the overall compensatory woodland area and improve habitat quality and ecological connectivity with adjacent woodland habitats.

Minimization of slope cutting through adoption of elevated alignment

14.2.1.8 Given the hilly terrain to the south of NTM NDA, the road alignment has been elevated. This adjustment not only minimises the scale of site formation works, but also takes into account other constraints, such as the clearance requirement for CLP power cables. Additionally, a larger headroom would provide greater clearance between the structure and the habitats so as to allow natural sunlight to shine on the habitats underneath the viaduct structures.

Minimisation of slope cutting through soft ground tunnelling at portals

14.2.1.9 When the alignment passes through Ngau Tam Shan and Hadden Hill, soft ground tunnelling has been adopted at portals. Specifically, before the tunnel excavation reaches bedrock, soft soil stratum will be improved with injection grouting around the tunnel profile. Temporary support such as pipe roofing and steel lattice girder/rib will be installed during the tunnel excavation by mechanical method. With the adoption of soft ground tunnelling, the extent of site formation is significantly reduced, which helps retain a larger area of natural terrain and minimise the generation of construction and demolition (C&D) materials.

Minimisation of slope cutting through construction of retaining walls and soil nailing

14.2.1.10 For sections where extensive cut slopes would otherwise be required, retaining walls / soil nails or combination of both may be proposed. This measure aims to reduce the extent of slope excavation, allow for steeper slope gradients, and thereby minimise the project's environmental footprint, as well as acting as a barrier to prevent wildlife roadkill.

Avoidance of direct impacts on Sites of Archaeological Interest (SAI)

14.2.1.11 Avoid any excavation works which will cause potential disturbance to the soil matrix within the boundary of Ngau Tam Mei SAI to avoid potential direct impacts on the SAI.

Adopt Drill and Blast (D&B) method for tunnel construction

14.2.1.12 Adopt Drill and Blast (D&B) method over TBM (Tunnel Boring Machine) method for tunnel construction to minimize the generation of C&D materials as much as practicable.

14.2.1.13 Diverting the existing traffic flow between northeast and northwest of the New Territories, lowering vehicular emissions from idling or congested traffic and shortening travel times and results in further reducing fuel consumption, alleviating potential air quality and noise impact during operation phase.

14.3 Other Environmental Design Recommended

14.3.1.1 Other than the initiatives to avoid environmental impacts as summarized in **Section 14.2**, further efforts have been exercised to minimize impacts. The need for environmental designs required to mitigate the associated impacts have also been identified and will be implemented as appropriate. A summary of these approaches is given below:

- Adoption of environmentally friendly construction method and phased construction arrangements;
- Implementation of trip-ticket system and GPS or equivalent system; and

- Implementation of environmental monitoring and audit system.

Adoption of Environmentally Friendly Construction Method and Phased Construction Arrangements

14.3.1.2 To minimize on-site work and its associated environmental impacts, such as potential air quality and noise impact from construction activities, as well as C&D waste generation, precast prestressed concrete construction methods will be generally employed. This approach shall be adopted for the construction of viaducts, piles/piers, and building works as far as practicable.

14.3.1.3 The precast concrete girder would be manufactured in casting yard offsite and transported to site for final positioning and stitching. In addition, the phased construction arrangement would also help to minimise the cumulative environmental impacts and to avoid intense, simultaneous pollution.

Implementation of trip-ticket system and GPS or equivalent system

14.3.1.4 In order to monitor, document and verify the disposal of C&D materials at landfills and public fill reception facilities, and to control fly tipping, a trip-ticket system for disposal of C&D materials would be implemented. Adopting GPS or equivalent system for tracking and monitoring of all dump trucks for the Project to record their travel routings and parking locations to prohibit illegal dumping and landfilling of C&D materials.

Implementation of environmental monitoring and auditing system

14.3.1.5 In addition to the mitigation measures as described above (see more details in the Implementation Schedule of Recommended Mitigation Measures as given in the stand-alone EM&A Manual), a comprehensive environmental monitoring and auditing programme would be implemented to cover various aspects of concerns. An Environmental Team would be employed to conduct the EM&A programme and ensure the Contractor's compliance with the project's environmental performance requirements during construction. An Independent Environmental Checker would also be employed to ensure that all the necessary mitigation measures are implemented in a timely and orderly manner.

14.4 Key Environmental Problem Avoided and Environmentally Sensitive Areas Protected

14.4.1.1 This section summarises the key environmentally friendly designs adopted in the recommended alignment to avoid, minimise and mitigate environmental impacts. Some of these approaches have contributed to avoid a number of environmental problems and to protect a number of environmentally sensitive areas and are presented in **Table 14.1** below.

Table 14.1 Summary of Key Environmental Issues Avoided / Minimised and Sensitive Areas Protected

Design Approaches	Environmental Issues Avoided/Minimised and Sensitive Areas Protected
Avoidance of ecologically sensitive areas	• The current alignment avoids encroaching ecologically sensitive areas such as Lam Tsuen Country Park, the proposed Nam Sang Wai Wetland Conservation Park and natural

Design Approaches	Environmental Issues Avoided/Minimised and Sensitive Areas Protected
	watercourses at Ngau Tam Mei, thereby avoiding potential ecological impact. • The current alignment avoids encroaching the existing bat roost and planned bat shelter at Pok Wai, thereby avoiding the direct ecological impact to bats. • Locations of piers also designed to avoid direct encroachment into natural watercourses
Relocation of I/C-03 to South of Ngau Tam Mei to avoid wetland habitat near Ngau Tam Mei Water Treatment Works (NTMWTW)	• The location of I/C 03 has been relocated from near the existing NTMWTW to near the South of Ngau Tam Mei NDA such that the direct impact to the pond and marsh habitats near NTMWTW has been minimised.
Avoid Habitat Isolation and Fragmentation and Roadkill Using Intermittent At-grade and Viaduct Design	• Adopt viaduct design as much possible to avoid habitat fragmentation and isolation at Lam Tsuen Country Park • For at-grade sections, retaining wall on the slope would be constructed to avoid wildlife roadkill
Viaduct Level Arrangement and Carriageway Separation for Enhancing Sunlight Penetration and Ecological Benefits	• Viaduct structures crossing wetland habitats are designed with specific height and width ratios and adequate headroom to minimize shading effect and allow optimal sunlight penetration • Piers are designed to avoid direct encroachment onto natural streams
Adoption of non-dredged method for works at Kam Tin River	• Minimised the disturbance to the riverbed • Minimised the impact to the water quality
Synergistic Woodland Compensation near She Leng	• Enhance the habitat connectivity and quality of She Leng through off-site woodland compensation
Minimization of slope cutting	• Minimised disruption to the landscape resources and characters • Minimised potential impacts to the natural habitats and associated ecology • Minimised the amount excavation spoil and generation of C&D materials
Avoidance of direct impacts on Sites of Archaeological Interest (SAI)	• Avoid any excavation works which will cause potential disturbance to the soil matrix within the boundary of Ngau Tam Mei SAI to minimize the potential archaeological impact.
Adopt Drill and Blast (D&B) method for tunnel construction	• Adopt D&B method over TBM method to minimize the generation of C&D materials
Adoption of environmentally friendly construction methods and phased construction	• Adoption of off-site precast structures / modular integrated construction method to minimise the impacts on air quality, noise, water quality and waste during construction. • Adopt phased construction arrangement to minimise the cumulative environmental impacts. • Implementation of 100m buffer area from the existing Sha Po Ardeid Night Roost, where timing control on the use of noisy construction activities would be implemented to minimize disturbance to the night roost.

Design Approaches	Environmental Issues Avoided/Minimised and Sensitive Areas Protected
Implementation of 'no work zone' for minimization of habitat loss	• Minimised the impacts and disturbance to ecologically sensitive areas and resources
Avoidance of illegal dumping	• The recommended preventive measures, such as real time tracing and monitoring of their travel routings and parking locations of the dump trucks through GPS or equivalent system, would avoid / minimise the chance of illegal dumping.
Implementation of Environmental Monitoring and Auditing System	• Ensure all the recommended measures are properly in place and their effectiveness.

14.5 Environmental Protection Measures Recommended

14.5.1.1 Mitigation measures were recommended to further reduce the environmental impacts due to the construction and operation of the Project. Key recommended mitigation measures / good site practices / enhancement measures and their associated benefits are summarised in **Table 14.2** below.

Table 14.2 Summary of Key Recommended Mitigation Measures / Good Site Practices / Enhancement Measures and their Associated Benefits

Environmental Aspect	Key Recommended Mitigation Measures / Good Site Practices / Enhancement Measures	Associated Benefits
Air Quality	Construction Phase • Implementation of control measures as required in the Air Pollution Control (Construction Dust) Regulation to minimise construction air quality impact. • Incorporation of Guidelines stipulated in EPD's Recommended Pollution Control Clauses for Construction Contracts in the contract documents • Timely application of temporary electricity and water supply and adoption of electric vehicles in accordance with DEVB TC(W) No. 13/2020 – Timely Application of Temporary Electricity and Water Supply for Public Works Contracts and Wider Use of Electric Vehicles in Public Works Contracts • Installation of a blast door at the opening to avoid the escape of fugitive dust from the blasting. The blast door should remain closed and ventilation with dust filter of at least grade F8 in accordance with EN 779:2012 or grade E11 as per EN 1822. • The approved non-road mobile machinery (NRMMs) under the Air Pollution Control (Non-road Mobile Machinery) (Emission) Regulation (excluding exempted NRMMs) would be used on-site and NRMMs supplied with mains electricity instead of diesel-powered should be adopted as far as possible to minimise the potential emission from NRMMs. Operation Phase • No mitigation measures would be required.	• Protect Air Sensitive Receivers (ASRs) by reducing air pollutants emissions. • Ensure compliance with the requirements in Section 1 of Annex 4 of the EIAO-TM at the ASRs
Noise	Construction Phase: • Implementation of quality and quieter powered mechanical equipment (PME), temporary / movable noise barriers and enclosure to screen off noise from relatively static PMEs, quieter construction methods, temporary movable noise barriers, noise enclosures, silencers as well as good site practices during construction phase of the Project to miminise construction noise impact. • For village houses / temporary structure with residential use which are close to the construction sites, it is recommended to install site hoarding with higher surface density and height to provide extra noise attenuation to protect these NSRs. • Submission of Construction Noise Management Plan (CNMP) before tender	• Protect Noise Sensitive Receivers (NSRs) by reducing construction, fixed noise source and road traffic noise impacts. • Ensure compliance with the respective road traffic noise requirements at neighbouring NSRs.

Environmental Aspect	Key Recommended Mitigation Measures / Good Site Practices / Enhancement Measures	Associated Benefits
	invitation. Operation Phase: • Implementation of Low Noise Road Surfacing (LNRS), noise barrier and at-receiver mitigation measures such as acoustic windows/balconies to alleviate road traffic noise impact on surrounding NSRs. • Submission of Fixed Noise Sources Management Plan (FNMP) before issuance of tender.	
Water Quality	• Construction of pier and viaduct structures across Kam Tin River would require installation of cofferdam and/or watertight pile casing to enclose the construction works. Cofferdam and watertight pile casing should be constructed to isolate the construction activities from the river water. Cofferdams should be designed by the Contractor which fulfil the requirements in DSD Technical Circular No. 1/2017 "*Temporary Flow Diversions and Temporary Works Affecting Capacity in Stormwater System*". • Pier construction at Kam Tin River should be conducted by phases to avoid adverse water flow impact due to flow blockage increase during the interim construction stages. • Water pumps should be used to collect any construction site runoff and ingress/seepage water within the cofferdam and watertight pile casing to the on-site wastewater treatment facilities for treatment to satisfactory levels before discharge. • Silt curtain should be deployed to completely enclose the cofferdam and watertight pile casing prior to conduct construction works in Kam Tin River, and installation and removal of cofferdam and watertight pile casing. • Mitigation measures and good site practices in ProPECC PN 2/24 "*Construction Site Drainage*" • Practices in ETWB TC (Works) No. 5/2005 "*Protection of natural streams / rivers from adverse impacts arising from construction works*" • Waste Disposal Regulation (Cap. 354) • Provision of interim treatment facilities, such as chemical toilets, for construction workforce • Stormwater Management Practices and Stormwater Pollution Control Plan to reduce non-point source pollution.	• Minimize potential water quality impacts from construction activities, including construction works in Kam Tin River, construction site runoff, wastewater generated from general construction activities, accidental spillage of chemicals, sewage from construction workforce, construction works near watercourses, removal / diversion of watercourses, removal / filling of ponds, groundwater infiltration arising from tunnel boring, groundwater from contaminated areas, contaminated site run-off and wastewater from land decontamination. • Minimize potential water quality impacts from non-point source surface run-off

Environmental Aspect	Key Recommended Mitigation Measures / Good Site Practices / Enhancement Measures	Associated Benefits
	• Adequate design in silt trap for the new road drainage which take into account the guidelines in ProPECC PN 1/23 "*Drainage Plan subject to Comments by the EPD*".	
Waste Management Implications	• Implementation of good site practices and waste reduction measures (e.g. reuse of C&D materials before off-site disposal or develop a materials recovery and recycling programme during construction and operation). • A Construction and Demolition Material Management Plan should be prepared in accordance with Section 4.1.3 “Construction and Demolition Materials” of the *Project Administration Handbook for Civil Engineering Works* (*PAH*). • Preparation of a Waste Management Plan, as part of the Environmental Management Plan by Contractor for Project Manager’s approval. • Implement a trip-ticket system for each works contract in accordance with *DEVB TC(W) No. 6/2010* to ensure that the disposal of C&D materials is properly documented and verified. • Handling of chemical waste in accordance with the Code of Practice on the Packaging, Labelling and Storage of Chemical Wastes, and disposal of chemical waste at licensed chemical waste treatment and disposal facilities. • General refuse should be stored in enclosed bins or compaction units separately from C&D materials and chemical wastes. • An enclosed and covered area is preferred to reduce the occurrence of wind-blown light materials. • The recyclable component of general refuse, such as aluminium cans, paper and cleansed plastic containers shall be separated from other wastes. • Remaining non-recyclable refuse should be disposed of at NENT Landfill, separate from chemical wastes, on a daily basis by a reputable waste collector. • The Contractor shall carry out an education programme for workers in avoiding, reducing, reusing and recycling of materials generation. Posters and leaflets advising on the use of the bins shall also be provided in the sites as reminders. The recyclable waste materials should then be collected by reliable waste recycling agents on a regular basis. • The Contractor is encouraged to deliver waste materials to EcoPark and Y·PARK for reuse and recycling, especially for yard wastes generated during site clearance.	• Minimise waste generation and off-site disposal. • Ensure the C&D materials are disposed of and delivered to designated sites. • Minimise hygiene issues. • Ensure proper handling of chemical waste. • Ensure proper waste management, treatment and reuse/disposal of excavated sediment.

Environmental Aspect	Key Recommended Mitigation Measures / Good Site Practices / Enhancement Measures	Associated Benefits
	• On-site reuse of excavated sediment (e.g. as backfilling materials) is proposed to minimise off-site disposal. • The excavated sediment would be treated by cement stabilization / solidification (S/S) to improve the material strength to render it suitable for reuse. • For off-site disposal of sediments, follow the requirements and procedures specified under paragraph 4.2.1 of Chapter 4 of the *PAH and DASO*.	
Land Contamination	• Subject to the finding of Contamination Assessment Plan / further site appraisal and Contamination Assessment Report (CAR), if contamination is identified, the remediation measures for remediation works as stated in Remediation Action Plan(s) should be implemented to ensure soil / groundwater contamination, if any, would be identified and properly remediated prior to construction works. • With reference to previous studies, natural occurrences of elevated level of arsenic exist over broad areas of the northern New Territories. A separate arsenic assessment and remediation plan should be prepared, in consultation with EPD, and submitted to EPD for endorsement prior to the commencement of construction works.	• Identify and treat, if necessary, the land contamination identified prior to the construction works to avoid potential risk to workers and future occupants.
Ecology	<u>Construction Phase:</u> • Avoidance of direct impact to recognized sites of conservation importance such as the Lam Tsuen Country Park and other ecologically sensitive resources such as the Proposed Nam Sang Wai Wetland Conservation Park by thorough consideration and evaluation of alignment options and careful design on the locations of the piers. • Implementation of no work zone and phased construction to minimize habitat loss • Noisy works within 100 m from the Sha Po ardeid night roost should be avoided from one hour before sunset to one hour after sunrise. • Piling works at the Kam Tin River would be scheduled to conduct during high tidal level (i.e. above 1.0 mCD) during dry season when the riverbed of the Kam Tin River would be mostly submerged. • Conduct pre-construction survey and transplantation / translocation for flora/fauna species of conservation importance. • Provide wetland compensation site and woodland compensation site. • Provide proper screening (e.g. hoarding or barrier) to restrict, confine, and demarcate the construction activities within the Project Boundary, and to avoid the wildlife from accidentally entering the boundary.	• Avoid and/or minimise direct impacts on recognised sites of conservation importance and other ecologically sensitive resources • Minimize potential disturbance to the Sha Po ardeid night roost • Compensate for the unavoidable loss of marsh/reed, ponds, modified watercourse, and woodland • Avoid and/or minimize wildlife species from entering construction site • Minimize bird collision • Avoid and/or minimise night-time disturbance • Avoid and/or minimise potential noise, air and water quality impact • Minimize and prevent roadkill of animals

Environmental Aspect	Key Recommended Mitigation Measures / Good Site Practices / Enhancement Measures	Associated Benefits
	• Adopt general good site practice, noise, air and water quality mitigation measures. • Provide suitable lighting in construction sites, use directional lighting and control night-time lighting period. <u>Operation Phase:</u> • Non-transparent panels should also be used as noise enclosure, as well as adopting non-glaring tinted materials, or superimposing dark patterns at the majority of glazing along noise barriers. • Implementation of animal barrier	
Fisheries	<u>Construction Phase:</u> • Maintaining bund stability • Minimisation of potential water quality impacts • Control of construction site run-off • Control of construction-related activities • Implementation of good site practices	• Minimising impact of construction works on the stability of fishpond bund and potential seepage from nearby fishponds into excavation area.
Landscape and Visual	<u>Construction Phase:</u> • Tree Preservation and Transplantation • Erection of Decorative Screen Hoarding • Management of Construction Activities and Facilities • Reinstatement of the Affected Landscaped Area • Minimize the Direct Conflict with Lam Tsuen Country Park • Minimize Disturbance on Watercourses/Wetlands <u>Operation Phase:</u> • Aesthetically Pleasing Design of Aboveground Structures • Aesthetically pleasing design of Highways Structures and Slope Associated Structures • Compensatory Tree Planting • Buffer Screen Planting / Roadside Planting	• Minimise landscape impacts on surrounding setting • To blend in the structure to the adjacent environment and visual context. • To provide screening to and soften the hard edges of the proposed structures and mitigate the potential visual impact to key public viewers. • To compensate felled trees. • To enhance the landscape quality of the proposed buildings and mitigate any potential visual impact on adjacent visual sensitive receivers

Environmental Aspect	Key Recommended Mitigation Measures / Good Site Practices / Enhancement Measures	Associated Benefits
	• Landscape Treatments on Slope or Retaining Structure • Post-Planting Monitoring • Reinstatement of disturbed Open Space • Incorporation of Green Roof • Sensitive design of noise barriers	
Cultural Heritage	Construction Phase: • No sub-soil disturbance works would be carried out within the Ngau Tam Mei SAI. • If the work arrangement deviates from the current proposed situations, an archaeological survey-cum-excavation should be carried out to obtain archaeological data for assessing the impact before commencement of the works, in consultation with the AMO, and to design mitigation measure as appropriate. • Pursuant to the Antiquities and Monuments Ordinance (Cap. 53), the project proponent is required to inform the Antiquities and Monuments Office (AMO) immediately in case of discovery of antiquities or supposed antiquities in the course of works, so that appropriate mitigation measures, if needed, can be timely formulated and implemented in agreement with and to the satisfaction of AMO.	• To avoid or minimise the potential impacts to the concerned SAI.
Hazard to Life	• Implement the good practices to minimize the potential risks even further and ensure that the services, utilities, slopes, retaining walls, buildings and structures will not be affected through ground vibrations or other effects. • Blasting Works: The good practice could make reference to the latest guideline including, but not limited to, Practice Note for Authorized Persons and Registered Structural Engineers (APP-72) by Buildings Department (BD). • Overnight Storage of Explosives: The good practice could made reference to the latest guideline including, but not limited to, “Guidance Note No. GN 8 How to Apply for a Mode A Store Licence for Storage of S1DG (Blasting Explosives)” by CEDD. • Transportation of Explosives: The good practice could made reference to the latest guideline including, but not limited to “Guidance Note No. GN 2 Approval of an Explosives Delivery Vehicle” and “Guidance Note No. GN 3 Application and Handling of a Conveyance Permit” by CEDD.	• Protect nearby sensitive receivers due to transportation, storage and use of explosive.

14.6 Population and Environmentally Sensitive Areas Protected

14.6.1.1 The Project has avoided encroachment into ecological sensitive areas, including Lam Tsuen Country Park and the proposed Nam Sang Wai Wetland Conservation Park, with careful Project planning and design. Moreover, based on the EIA Study, with proper mitigation measures in place, the population in vicinity of the Project and along the main alignment (e.g., the planned residential developments along the existing San Tin Highway, Sha Po, Mo Fan Heung, NTM NDA, etc.) will be protected. No adverse environmental impacts are anticipated during either the construction or operation phases.

[BLANK PAGE]